



G
S
C
W
U

**The Government
Sadiq College Women
University Bahawalpur Pakistan**

TENDER NOTICE


Sealed tenders on prescribed tender forms are invited on the basis of MRS (MRS 1st BI-Annual-2018 1st January to 30-June 2018) % age / item rates for the works mentioned below from the contractors/firms enlisted/renewed with Government Sadiq College Women University, Bahawalpur for the current financial Year.

Sr. No	Name of works	Estimated Cost Rs.	Earnest Money Rs.	Tender Form Fee Rs.	Period
1	Construction of Extension of Habib Bank Limited, Sadiq Women University Branch, The Govt: Sadiq College Women University, Bahawalpur.	Rs 9,57,900/-	19,158/-	10,000/-	6-Months

1. Detailed particular of the works can be seen in the office of the undersigned on the working days during office hours.
2. Prescribed tender forms duly signed by the undersigned can be obtained from the office of the undersigned upto 24-01-2018 during office hours, upon provision of
 - i. Bank Receipt of Tender form Fee.
 - ii. Deposit at call as earnest money @2% of estimated cost from any scheduled bank issued in the name of Treasurer, The Govt. Sadiq College Women University Bahawalpur must be accompanied with the tender.
 - iii. Proof of Enlistment of contractor /firm in the Government Sadiq College Women University, Bahawalpur for the current year.
3. Tender will be issued to the owner of the firm/ contractor himself OR their authorized representative.
4. The tender form will be issued, received and opened as per following schedule:

i.	Date of issue of tender form	Up to 24-01-2018
ii.	Date of Receiving	13-02-2018 at 11:00 AM
iii.	Date & Timing of Opening	13-02-2018 at 11:30 AM

5. This Tender notice can also be seen at the PPRA website www.ppra.punjab.gov.pk & GSCWU website www.gscwu.edu.pk.
6. Tender will be opened by tender opening committee in the office of undersigned GSCWU in the presence of contractors/their authorized representatives.
7. The GSCWU reserves the right to cancel/reject all tenders/bids at any time prior to the acceptance of bids or proposal in accordance with rule 35 of Punjab Procurement Rules, 2014. However, the procuring agency shall upon request communication to any bidder, the grounds for its rejection of all bids proposal, but shall not be required to justify those ground.


Executive Engineer
The Govt. Sadiq College Women
University Bahawalpur.

The Govt. Sadiq College Women University Bahawalpur

Construction of Extension of Habib Bank Limited, Sadiq Women University Branch, The Govt. Sadiq College Women University Bahawalpur

(MRS 1st BI-Annual-2018 1st January to 30th June, 2018 and input rates)


Sr. No	Description	Quantity	Rate	Unit	Amount
1	Excavation in foundation of building, bridges and other structures, including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead up to one chain (30 m) and lift upto 5 ft. (1.5 m) in ordinary soil.	694 Cft		%0 Cft	
2	Spraying anti-termite liquid mixed with water in the ratio of 1:40.	3023 Sft		%Sft	
3	Cement concrete brick or stone ballast 1½ " to 2" in foundation and plinth:-	183 Cft		%Cft	
4	Pacca brick work (1:6) in foundation and plinth Cement Sand Mortar	367 Cft		%Cft	
5	Providing and laying damp proof course of cement concrete 1:2: 4(using cement, sand and shingle), including bitumen coating (a) with one coat bitumen and one coat polythene sheet 500 gauge 1½" thick (40 mm)	8 Sft		%Sft	
6	6. Two coats of bitumen laid hot using 34 lbs. per %Sft, or 1.72 Kg per square meter over roof and blinded with sand at one Cft. per %Sft including Supplying and laying polythene sheet over D.P.C. under floors and on roofs, etc. 500 gauge (.005" thick)	181 Sft		%Sft	
7	Filling, watering and ramming earth under floors with surplus earth from foundation, etc	463 Cft		%0 Cft	
8	Filling, watering and ramming earth under floors with new earth excavated from outside, lead upto 5 miles & lift upto 5'	313 Cft		%0 Cft	
9	9. Providing and laying reinforced cement concrete (including prestressed concrete), using coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete (but excluding the cost of steel reinforcement, its fabrication and placing in position, etc.) Type B (nominal mix 1:2:4)	489 Cft		Per Cft	

10	Fabrication of mild steel reinforcement for cement concrete, including cutting, bending, laying in Position, making joints and fastenings, including cost of binding wire and labour charges for binding of steel reinforcement (also includes removal of rust from bars):- Deformed bars (Grade-40)	2220 KG	%KGs	
11	Pacca brick work in ground floor Ratio(1:6)	530 Cft	%Cft	
12	Cement plaster, cement sand mortar upto 20' height	599 Sft	%Sft	
	(a) 3/4" thick(1:5)	8194 Sft	% Sft	
	(b) 1/2" thick (1:4)	599 Sft	% Sft	
13	Single layer of tiles 9"x4½"x1½" (225x113x40 mm) laid over 4"(100 mm) earth and 1" (25 mm) mud plaster without Bhoosa, grouted with cement sand 1:3 on top of RCC roof slab, provided with 34 lbs. per %Sft. or 1.72 Kg/Sq.m bitumen coating sand blinded.	332 Sft	%Sft	
14	Providing and fixing and tisting UPVC 4" dia nikasi Type 'B' with solution of same quality make (dadex/ Beeta/BBJ or equivalent	13 Rft	Per Rft	
15	Providing and fixing special plain bend 4" i/d (dadex/ Beeta/BBJ or equivalent	1-No	Each	
16	Khurras on roof 2'x2'x6" (600 x 600 x 150 mm)	1-No	Each	
17	Bottom Khurras of brick masonry in cement mortar 1:6, 4'x2'x4½" (1200x600x113 mm) over 3" (75 mm) cement concrete 1:4:8.	1-No	Each	
18	Providing and fixing all types of partly fixed and partly openable glazed anadised bronze colour aluminium doors, using delux section of M/S Al-cop of Pakistani cables, having chowkat frame of size 40x100 mm (1½"x4) and leaf frame of 60x40mm (2 ½"x1 ½") wide sections including the cost of ¼" (5mm) thick imported tinted glass with aliminium triangular gola and rubber gasket to support the glass and leaf edging, using approved standard fittings, locks, 3" (75mm) wide long handles etc. and hardware any required as approved by the engineer in-charge.	25 Sft	Per Sft	
19	Supplying and filling sand under floor; or plugging in wells.	129 Cft	% Cft	
20	Providing, laying, watering and ramming brick ballast 1½" to 2"(40 mm to 50 mm) gauge mixed with 25% sand, for floor foundation, complete in all respects.	129 Cft	%Cft	

21	Cement concrete plain including placing, compacting, finishing and curing complete (including screening and washing of stone aggregate):	65 Cft	%Cft	
22	Providing and fixing glazed double door consisting of frame of aluminum channel 2mm thick top and bottom and u in sides (D48A) 2mm thick glass Ghani or equivalent, 2-sets handles, lock, hinges, machine 2-Nos and hard ware items complete in all respect as approved by the engineer incharge	1-Job	Per Job	
23	23. Providing and fixing 12mm thick glass Ghani or equivalent in aluminum channel 2 mm thick on top and bottom and U in sides (D48A) for frame with hard ware items complete in all respects as approved by the engineer in-charge	84 Sft	Per Sft	
Total				


SUB ENGINEER


Assistant Engineer
The Govt. Sadiq College
Women University,
Bahawalpur.


Executive Engineer
The Govt. Sadiq College
Women University,
Bahawalpur.
24/1/18