



**The Government
Sadiq College Women
University Bahawalpur Pakistan**

TENDER NOTICE


Sealed tenders on prescribed tender forms are invited on the basis of MRS (MRS 1st BI-Annual-2018 1st January to 30-June 2018) % age / item rates for the works mentioned below from the contractors/firms enlisted/renewed with Government Sadiq College Women University, Bahawalpur for the current financial Year.

Sr. No	Name of works	Estimated Cost Rs.	Earnest Money Rs.	Tender Form Fee Rs.	Period
1	Making and Fixing Stainless Steel Logo of Gscwu on Front of Academic Block, The Govt: Sadiq College women University, Bahawalpur.	Rs 2,02,800/-	4,100/-	102/-	1-Month
2	Construction of Stove Shed of Mariyam Hostel Kitchen, The Govt: Sadiq College Women University, Bahawalpur.	Rs 1,03,900/-	2,100/-	52/-	1-Month

- Detailed particular of the works can be seen in the office of the undersigned on the working days during office hours.
- Prescribed tender documents duly signed by the undersigned can be obtained from the office of the undersigned upto 10-07-2018 during office hours, upon provision of
 - Bank Receipt of Tender form Fee.
 - Deposit at call as earnest money @2% of estimated cost from any scheduled bank issued in the name of Treasurer, The Govt. Sadiq College Women University Bahawalpur must be accompanied with the tender.
 - Proof of Enlistment of contractor /firm in the Government Sadiq College Women University, Bahawalpur for the current year.
- Tender will be issued to the owner of the firm/ contractor himself OR their authorized representative.
- The tender form will be issued, received and opened as per following schedule:

i.	Date of issue of tender form	Up to 10-07-2018
ii.	Date of Receiving	13-07-2018 at 11:00 AM
iii.	Date & Timing of Opening	13-07-2018 at 11:30 AM

- This Tender notice can also be seen at the PPRA website www.ppra.punjab.gov.pk & GSCWU website www.gscwu.edu.pk.
- Tender will be opened by tender opening committee in the office of undersigned GSCWU in the presence of contractors/their authorized representatives.
- The GSCWU reserves the right to cancel/reject all tenders/bids at any time prior to the acceptance of bids or proposal in accordance with rule 35 of Punjab Procurement Rules, 2014. However, the procuring agency shall upon request communication to any bidder, the grounds for its rejection of all bids proposal, but shall not be required to justify those ground.


Executive Engineer
The Govt. Sadiq College
Women University Bahawalpur.

**MAKING AND FIXING STAINLESS STEEL LOGO OF GSCWU ON FRONT OF ACADEMIC BLOCK,
GSCWU, BAHAWALPUR.**

Item No.	Description of Items	Unit	Qty	Rate (Rs.)	Amount (Rs.)
	MRS 1st BI-Annual-2018 (1st January To 30 June & input Rates)				
1	Making and fixing stain less steel LOGO 4.50'x3.75' size and Words The Govt. Sadiq College Women University. Bahawalpur (URDU letters) and fixed steel etching block on allocobond sheet 5mm. thick 24'x6' size on iron frame complete in all respects as approved by the competent authority.	Each	1-No		
	G.Total				

M. Q. I.
SUB ENGINEER

[Signature]
Assistant Engineer
The Govt. Sadiq College
Women University,
Bahawalpur.


[Signature]
Executive Engineer
The Govt. Sadiq College
Women University,
Bahawalpur.


Construction of Store Shed of Mariyam Hostel Kitchen, GSCWU, Bahawalpur.

Item No.	Description of Items	Unit	Qty	Rate (Rs.)	Amount (Rs.)
MRS 1st BI-Annual-2018 (1st Januray To 30 June)					
1	Dismantling cement concrete 1:2:4 plain	100 Cft	6.00		
2	Excavation in foundation of building, bridges and other structures, including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead upto one chain (30 m) and lift upto 5 ft. (1.5 m) in ordinary soil.	100 Cft	120.00		
3	Cement concrete brick or stone ballast 1½ " to 2" (40 mm to 50mm) gauge. in foundation and plinth:-Ratio 1: 6:18	100 Cft	20.25		
4	Pacca brick work in foundation and plinth in:-Cement, sand mortar:-Ratio 1:6	100 Cft	9.21		
5	Providing and laying damp proof course of cement concrete 1:2:4(using cement, sand and shingle), including bitumen coating :- (a) with one coat bitumen and one coat polythene sheet 500gauge i) 1½" thick (40 mm)	100 Sft	2.53		
6	Filling, watering and ramming earth under floors:-with surplus earth from foundation, etc.	100 Cft	20.83		
7	Pacca brick work in ground floor:-cement, sand mortar:-Ratio 1:5)	100 Cft	32.25		
8	Cement plaster 1:4 upto 20' (6.00 mm) height:-½" (13 mm) thick	100 Sft	129.00		
9	Fabrication of heavy steel work, with angle, tees, flat iron round iron and sheet iron for making trusses, girders,tanks, etc., including cutting, drilling, revitting, handling,assembling and fixing,erection in position	100 Kgs	314.75		
10	Erection and fitting in position iron trusses, staging of water tanks, etc	100 Kgs	171.00		
11	Providing and laying reinforced cement concrete (including prestressed concrete), using coarse sand and screened graded and washed aggregate. in required shape and design, done for making up all surfaces including forms, moulds, shuttering, lifting, con.pacting,curing, rendering and finishing exposed surface, complete(but excluding the cost of steel reinforcement, its fabrication and placing in position, etc.):-(a)(ii) Reinforced cement concrete in slab of rafts / strip foundation, base slab of column and retaining walls; etc and other structural members other than those mentioned in 5(a) (i) above not requiring form work (i.e. horizontal shuttering) complete in all respects:-Type C (nominal mix 1: 2: 4)	P.Cft	3.80		
12	Fabrication of mild steel reinforcement for cement concrete,including cutting, bending, laying in position, making jointsand fastenings, including cost of binding wire and labour charges for binding of steel reinforcement (also includes removal of rust from bars):- Deformed bars (Grade-40)	100 Kgs	11.63		

13	Second class tile roofing consisting of 4" (100 mm) earth and 1" (25 mm) mud plaster with Gobri leaping over ½" (13 mm) thick cement plaster 1:6 with out bitumen coating sand blinded. provided over one layer of 12"x6"x2" (300x150x50 mm) tiles laid in 1:6 cement mortar, including 1:2 cement pointing underneath of tiles complete including curing, etc	100 Sft	255.00		
14	Single layer of tiles 9"x4½"x1½" (225x113x40 mm) laid without over 4"(100 mm) earth and 1" (25 mm) mud plaster without Bhoosa. grouted with cement sand 1:3 on top of RCC roof slab, provided without 34 lbs. per %Sft. or 1.72 Kg/Sq.m bitumen coating sand blinded.	100 Sft	260.00		
15	1½"(40 mm) thick mosaic flooring, consisting of ½ "(13mm) mosaic topping of one part of cement and marble powder in the ratio of 3:1 and two parts of marble chips,laid over 1"(25 mm) thick floor of 1:2:4 cement concrete,including rubbing and polishing complete with finishing :(a) using grey cement	100 Sft	131.69		
G.Total					


SUB ENGINEER


Assistant Engineer
The Govt. Sadiq College
Women University,
Bahawalpur.


Executive Engineer
The Govt. Sadiq College
Women University,
Bahawalpur.