



**The Government Sadiq College
Women University Bahawalpur
Pakistan**

TENDER DOCUMENTS

D.N.I.T/BOQ (SCHEME NO 1)

Construction of Cricket Pitch,GSCWU,BWP.

Item No.	Description of Items	Unit	Qty	Rate (Rs.)	Amount (Rs.)
MRS 1st BI-Annual-2024 (1st january To 30th June 2024)					
1	Filling, watering and ramming earth under floors:- ii) with new earth excavated from outside, lead upto 5 mile.	%0 Cft	19,000.00		
2	Dressing and levelling of earhtwork to designed section, etc.complete:- Ordinary or hard soil.	%0 Cft	19,000.00		
3	Compaction of earthwork (soft, ordinary or hard soil) :-ii) Compaction by rolling with animal driven roller/hand rammed :ordinary soil	%0 Cft	19,000.00		
4	Providing, laying, watering and ramming brick or stone ballast 1½ to 2"(40 mm to 50 mm) gauge mixed with 25% sand, for loor foundation, complete in all respects.	% Cft	600.00		
5	Pacca brick work other than building upto 10ft. (3 m) height. i) cement, sand mortar 1:5	%Cft	83.00		
6	Cement concrete plain including placing,compacting, finishing and curing complete (including screening and washing of stone aggregate):f Ratio 1: 2: 4	%Cft	51.00		
7	1-3/8"(35 mm) thick mosaic flooring, consisting of 3/8"(10 mm) mosaic topping of one part of cement and marble powder in the ratio of 3:1 and two parts of marble chips, aid over 1"(25 mm) thick flooring of 1:2:4 cement concrete including rubbing without polishing complete :- (a) using grey cement	% Sft	600.00		
8	Providing and fixing marble strip of any shade for dividing the mosaic flooring into panels a) Size 1½" x 3/8" (40 x 10 mm)	P.Rft	240.00		
9	Fabrication of heavy steel work, with angle, tees, flat iron round iron and sheet iron for making trusses, girders,tanks, etc., including cutting, drilling, revitting, handling,assembling and fixing, including erection in position.	% Kgs	1,109.00		
10	Providing and fixing mesh 2"x2" No.12 including cutting, drilling, revitting, handling,assembling and fixing	P.Sft	455.00		
11	Painting new surface:-Preparing surface and painting of fillets, framing, skirtings, pipes, gutters, and similar linear work not exceeding 6" (150 mm) girth .3 coats	% Rft	1,540.00		
12	Supply and erection of single core PVC insulated, PVC sheathed copper conductor, 250/440 volts grade cable (BSS-2004), in prelaid PVC pipes/M.S. conduit/G.I. pipe/wooden strip batten/wooden casing and capping/trenches, etc. (rate for cable only):-7/0.029"	P.mtr	90.00		
				Total	
				Add 5% Pst	
				G.Total	

D.N.I.T/BOQ (SCHEME NO 2)					
REPAIR/RENOVATION OF ADMAN BLOCK, GSCWU,BWP.					
Item No.	Description of Items	Unit	Qty	Rate (Rs.)	Amount (Rs.)
MRS 1st BI-Annual-2024 (1st January To 30th June 2024)					
1	Dismantling glazed or encaustic tiles, etc.	% Sft	1,010.00		
2	Cement plaster 1:4 upto 20' (6.00 m) height:-c) ¾" (20 mm) thick	% Sft	231.00		
3	Providing and laying superb quality Ceramic tile floors of Master brand of specified size,Glossy/Matt/Texture of approved Color and Shade as per approved design with adhesive bond, over ¾" thick (1:2) cement sand plaster i/c the cost of sealer for finishing the joints i/c cutting grinding complete in all respects and as approved and directed by the Engineer Incharge. i) 12"x18"/12"x24"/10"x24" /8"x24"/12"x36"	P.Sft	1,060.00		
4	Providing and laying superb quality Ceramic tiles dado of Master brand of specified size,Glossy/Matt/Texture skirting/dado of approved Color and Shade with adhesive bond over ½"thick (1:2) cement plaster i/c the cost of sealer for finishing the jointsi/c cutting grinding complete in all respects as approved and directed by the Engineer Incharge. i) 12"x18"/12"x24"/10"x24" /8"x24"/12"x36"	P.Sft	846.00		
5	Providing, fixing, testing and commissioning of µ-PVC (Unplasticized Polyvinyl Chloride) Nikasi/ SWV pipe, Dadex / Popular / Beta or approved equivalent manufacturer, plain / Bell Ended / Z - Joints conforming to BS 4514 / BS 5255 EN-1329 including the cost of specials and Solvents complete in all respects, as per drawings & specifications and / or as approved and directed by the Engineer Incharge.				
	(iv)3"(85 mm)	P.Rft	52.00		
	v)4"(110 mm)	P.Rft	39.00		
6	Providing, fixing, testing and commissioning of µ-PVC (Unplasticized Polyvinyl Chloride) Nikasi/ waste pipe Fittings make of Dadex Popular/Beta or approved equivalent manufacturer, conforming to code EN 329 including the cost of Solvents complete in all respect as approved and directed by the Engineer Incharge a)P-Trap				
	(ii) 3" dia	Each	8.00		
	(ii) 4" dia	Each	4.00		
7	Providing and fitting glazed earthen ware water closet, squatter type (Orisa pattern), combined with foot rest. i) white	Each	4.00		
8	Providing and fitting plastic made low down flushing cistern 13.63 litre (3 gallons) capacity, including bracket set, copper connection, etc. complete. i) white	Each	4.00		
9	Providing and fixing Bathroom Accessories (7-piece set) Master brand - One Cosmetic Shelf , One Towel rod with bracket, One soap dish, One double hook, One towel ring, brush holder, toilet paper holder & Looking glass i/c the cost of hardwares etc complete in all respect as approved and directed by the Engineer incharge.				
	i) Plastic soap dish	Each	2.00		
	iii) Plastic tower rail	Each	2.00		
	vi) Looking glass with plastic frame	Each	2.00		

10	Providing and fixing chromium plated stop cock, heavy:- i) 2 cm (¾")	Each	8.00		
11	Providing and fixing CP bath Room Set made of Sonex/Master/Faisal or approved equivalent manufacturer, comprising of 3-No Tee stop cocks, ever type Basin Mixer, double Bib Cock, open wall shower, Muslim shower,waste coupling and bottle trap etc. complete in all respect as approved and directed by the Engineer incharge				
	(iii) Double Bib Cock	Each	4.00		
	(ii) Lever Type Basin Mixer	Each	2.00		
	(v) Muslim shower	Each	4.00		
	(vi) Waste Coupling	Each	2.00		
12	Providing and fixing, angle iron brackets for: i) wash hand basin and cistern	Each	2.00		
13	Distempering 2 Coats old surface	% Sft	20,646.00		
14	Preparing surface and painting with emulsion paint:-(2-coats)	% Sft	55,202.00		
15	Painting old surfaces:- <u>Painting doors and windows, any type:</u>	% Sft	1,323.00		
16	Providing and applying weather shield paint of approved quality on external surface of building including preparation of surface, application of primer complete in all respect:	% Sft	8,589.00		
17	Preparing surface and Lacquer polish to reveal wooden grains by application of multiple coats of wood sealer , sand papering with different no of sandpapers and Lacquer to make glossy surface finish i/c the cost of cotton, thinner, wood sealer complete in all respects as approved and directed by the Engineer Incharge.(i) (ii) Glossy Finish	P.Sft	966.00		
					Total
					Add 16% Pst
					G.Total

D.N.I.T/BOQ (SCHEME NO 3)

REPAIR/ENOVATION OF ECONOMICS,BOTANY DIRECTORATE OF I.T,ISLAMIC STUDIES,PHYSICS CHEMISTRY,ZOOLOGY,& ORIC/QEC OFFICE,IC TLAB ,AND ENGINEERING DEPARTMENT,GSCWU,BWP.

Item No.	Description of Items	Unit	Qty	Rate (Rs.)	Amount (Rs.)
MRS 1st BI-Annual-2024 (1st January To 30th June 2024)					
1	Removing cement or lime plaster.	% Cft	1,324.00		
2	Dismantling lime concrete	%Cft	164.00		
3	Cement plaster 1:5 upto 20' (6.00 mm) height:-c) ¾	%Sft	721.00		
4	Providing and laying superb quality Ceramic tile floors of Master brand of specified size,Glossy/Matt/Texture of approved Color and Shade as per approved design with adhesive bond, over 3/4" thick (1:2) cement sand plaster i/c the cost of sealer for finishing the joints i/c cutting grinding complete in all respects and as approved and directed by the Engineer Incharge.i) 12"x18"/12"x24"/10"x24" /8"x24"/12"x36"	P.Sft	58.00		
5	Providing and laying superb quality Ceramic tiles dado of Master brand of specified size,Glossy/Matt/Texture skirting/dado of approved Color and Shade with adhesive bond over 1/2"thick (1:2) cement plaster i/c the cost of sealer for finishing the joints i/c cutting grinding complete in all respects as approved and directed by the Engineer Inchargei) 12"x18"/12"x24"/10"x24" /8"x24"/12"x36"	P.Sft	158.00		
6	Providing and fixing, double seat and cover only.ii) plastic.	Each	1.00		
7	Providing and fitting glazed earthen ware water closet, squatter type (Orisa pattern), combined with foot rest. i) white	Each	1.00		
8	Providing and fitting plastic made low down flushing cistern 13.63 litre (3 gallons) capacity, including bracket set, copper connection, etc. complete.i) white	Each	1.00		
9	Providing and fixing Bathroom Accessories (7-piece set) Master brand - One Cosmetic Shelf, One Towel rod with bracket, One soap dish, One double hook, One towel ring, brush holder, toilet paper holder & looking glass i/c the cost of hardwares etc complete in all respect as approved and directed by the Engineer incharge.				
	i) Plastic soap dish	Each	2.00		
	iii) Plastic tower rail	Each	2.00		
	vi) Looking glass with plastic frame	Each	2.00		
10	Providing and fixing chromium plated stop cock, heavy:- i) 2 cm (¾")	Each	6.00		
11	Providing and fixing chromium plated bib cock:- i) 2 cm (¾")	Each	2.00		
12	Providing and fixing CP bath Room Set made of Sonex/Master/Faisal comprising of 3-No Tee stop cocks, lever type Basin Mixer, double Bib Cock, open wall shower, Muslim shower,waste coupling and bottle trap etc. complete in all respect as approved and directed by the Engineer incharge.				

	(ii) Lever Type Basin Mixer	Each	2.00		
	(v) Muslim shower	Each	1.00		
	(vi) Waste Coupling	Each	1.00		
13	Distempering 2 Coats old surface	%Sft	8,648.00		
14	Preparing surface and painting with emulsion paint:-(2-coats)	%Sft	18,465.00		
15	Painting old surfaces:- Painting doors and windows, any type: Brushing and scraping blisters of old paints from woodwork. 2-Coats old Surface	%Sft	1,861.00		
16	Painting old surfaces:- Painting guard bars, gates of iron bars, gratings, railing (including standards, braces etc.) and similar open work:Scraping, brushing and removing old paint from metal surface. 2-Coats old Surface	%Sft	259.00		
17	Dismantling cement concrete 1:2:4 plain.	%Cft	40.00		
18	Dismantling brick work in lime or cement mortar	%Cft	30.00		
19	Providing and fixing 2" wide MS/ GI Chowkat singel/double rebate made of 16 SWG MS sheet pressed/welded / supported with M.S. flat 1-1/4"x1/8" i/c 6"long M.S. Flat 1"x1/8"hold fasts (6-Nos) welded/ screwed, punching of lock hole covered with MS Box,coating with antirust paint including filling with cement sand mortar (1:8) and embedding hold fast in cement concrete (1:2:4) ,complete in all respect as approved and directed by Engineer Incharge (ii) 10.50 " wide	P.Sft	28.00		
20	P/F 1-1/2" thick solid flush door comprising of 2.5 mm thick Commercial ply compressed over 2.5 mm thick commercial ply over 1" thick packing wood in style and rails under proper pressure i/c the cost of nails, tower bolt , handles, glue, sawing charges, Painting charges, sand papering and 3/8" thick matching wooden lipping as approved and directed by the Engineer Incharge.	P.Sft	46.00		
21	Cement plaster 1:4 upto 20' (6.00 m) height:-c) 1/2" (13 mm) thick	%Sft	990.00		
22	Fabrication of heavy steel work , with angle, tees, flat iron round iron and sheet iron for making trusses, girders, tanks, etc., including cutting, drilling, reviding, handling, assembling and fixing, but excluding erection in position.	%kgs	12.00		
23	P/F 3/4" dia heavy duty sliding bolt of specified material i/c the cost of hardware complete in all respect as approved and directed by the Engineer Incharge a) Iron ii) 12" (300 mm) long	Each	1.00		
24	Providing and laying superb quality Porcelain glazed tiles flooring of MASTER brand of specified size in approved design,Color and Shade with adhesive/bond over 3/4"thick (1:3) cement plaster i/c the cost of sealer for finishing the joints i/c cutting grinding complete in all respect as approved and directed by the Engineer Incharge. a) Full body Glazed tiles (i) 400 mm x 400 mm	P.Sft	801.00		
25	Providing and laying 3/4" thick full width Prepolished Marble slab for Vanities / Shelves / Treads/Window Cills , having Uniform texture (Spotless) with adhesive bond over 3/4" thick (1:2) cement sand mortar i/c the cost of matching sealer complete in all respect as approved and directed by the Engineer Incharge.i) China Verona	P.Sft	164.00		
				Total	
				Add 16% Pst	
				G.Total	

D.N.I.T/BOQ (SCHEME NO 4)					
CONSTRUCTION OF WASHROOMS FOR DAY CARE CENTER,GSCWU,BWP.					
Item No.	Description of Items	Unit	Qty	Rate (Rs.)	Amount (Rs.)
MRS 1st BI-Annual-2024 (1st January To 30th June 2024)					
1	Dismantling brick work in lime or cement mortar	% Cft	132.00		
2	Dismantling cement concrete 1:2:4 Plain	%Cft	48.00		
3	Excavation in foundation of building, bridges and other structures, including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead upto one chain (30 m) and lift upto 5 ft. (1.5 m) in ordin	%0 Cft	506.00		
4	Cement concrete brick or stone bal last 1½ " to 2" (40 mm to 50 mm) gauge, in foundation and plinth:- Ratio 1: 6:12	% Cft	69.00		
5	Pacca brick work in foundati on and plinth in:- Cement, sand mortar:- Ratio 1: 6	% Cft	295.00		
6	Providing and laying damp proof course of cement concrete 1:2: 4(using cement, sand and shingle), including bitumen coating :-(a) with one coat bitumen and one coat polythene sheet 500gauge ii) 2" thick (50 mm)	%Sft	47.00		
7	Filling, watering and ramming earth under floors:- i) with surplus earth from foundation, etc.	%0Cft	337.00		
8	Filling, watering and ramming earth under floors:- ii) with new earth excavated f rom outside, lead upto 5 mile.	%0Cft	245.75		
9	Pacca brick work in ground floor:- cement, sand mortar:- Ratio 1: 6	%Cft	492.00		
10	Fabrication of heavy steel work, with angle, tees, flat iron round iron and sheet iron for making trusses, girders, tanks, etc., including cutting, drilling, revitting, handling, assembling and fixing, including erection in position.	%Kgs	174.00		
11	Second class tile roofing consisting of 4" (100 mm) earth and without 1" (25 mm) mud plaster without Gobri leeping without over ½" (13mm) thick cement plaster 1:6 without 34 lbs. per %Sft or 1.72 Kg/sq.m of hot bitumen coating sand blinded, provided over one layer of 12"x6"x2" (300x150x50 mm) tiles laid in 1:6 cement mortar, including 1:2 cement pointing underneath of tiles complete including curing, etc.including supplying and laying polythene sheet over D.P.C. under floors and on roofs, etc pol ythene sheet 500 gauge (.005" thick)	%Sft	154.00		
12	Single layer of tiles 9"x4½"x1½" (225x113x40 mm) without laid over 4"(100 mm) earth and 1" (25 mm) mud plaster without Bhoosa, grouted with cement sand 1:3 on top of RCC roof slab, excluding with 34 lbs. per %Sft. or 1.72 Kg/Sq.m bitumen coating sand blinded .	%Sft	119.00		
13	1/2" thick Cement plaster 1:5 upto 20' (6.00 mm) height	%sft	864.00		
14	Providing and fitting all types of glazed aluminium windows of anodised/ powder coated partly fixed and partly sliding using delux sections of approved manufacturer having frame size of 100 x 30 mm (4"x1-1/4") and leaf frame sections of 50 x 20 mm (2"x¾"), all of 1.6mm thickness including 5 mm thick imported tinted glass with rubber gasket using approved standard latches, hardware etc., as approved by the Engineer in-charge.	P.Sft	12.00		

15	Providing and fixing UPVC Doors i/c Chowkat 38mm thickness i/c deluex matching color UPVC frame matt or glossy finish having color (white-Gray-Marble Gray-Oak Wood- Dard Oak Wood, Coffee Wood Honey Pine Wood-Mahagony-Marry Gold-Chocolate Brown-Honey Dew) i/c all accessories i/c mortice locks complete in all respect as approval by the Engineer Incharge.	P.Sft	17.50		
16	Providing and fixing 2" wide MS/ GI Chowkat singel/double rebate made of 16 SWG MS sheet pressed/welded / supported with M.S. flat 1-1/4"x1/8" i/c 6"long M.S. Flat 1"x1/8"hold fasts (6-Nos) welded/ screwed, punching of lock hole covered with MS Box,coating with antirust paint including filling with cement sand mortar (1:8) and embedding hold fast in cement concrete (1:2:4) ,complete in all respect as approved and directed by Engineer Incharge.(ii) 10.50 " wide	P.Sft	21.00		
17	Providing, laying, watering and ramming brick ballast 1½" to 2"(40 mm to 50 mm) gauge mixed with 25% sand, for floor foundation, complete in all respects.	% Cft	86.38		
18	Providing and laying topping of cement concrete 1:2:4,including surface finishing and dividing in panels:-(e) 2"(50 mm) thick	P.Sft	120.00		
19	Preparing surface and painting with emulsion paint:- 2 Coats	%Sft	248.00		
20	Providing and applying weather shield paint of approved quality on external surface of building including preparati on of surface, application of primer complete in all respect: new surface	%Sft	432.00		
21	Providing and laying superb quality Ceramic tile floors of Master brand of specified size,Glossy/Matt/Texture of approved Color and Shade as per approved design with adhesive bond, over 3/4" thick (1;2) cement sand plaster i/c the cost of sealer for finishing the joints i/c cutting grinding complete in all respects and as approved and directed by the Engineer Incharge i) 12"x18"/12"x24"/10"x24" /8"x24"/12"x36"	P.Sft	122.88		
22	Providing and laying superb quality Ceramic tiles dado of Master brand of specified size,Glossy/Matt/Texture skirting/dado of approved Color and Shade with adhesive bond over 1/2"thick (1:2) cement plaster i/c the cost of sealer for finishing the joints i/c cutting grinding complete in all respects as approved and directed by the Engineer Incharge i) 12"x18"/12"x24"/10"x24" /8"x24"/12"x36"	P.Sft	320.00		
23	P/ Lfalse ceiling comprising of 5/8" thick plaster of paris sheet of required size in approved design with one line of 6" wide che all around , hanging with Copper wire (16 SWG) duly enriched with POP and flaxen i/c the cost of making space for rope light /screws/jute/making holes for lights and rawal plugs complete in all respects as approved and directed by the Inchar ge. (Measur ement will be made as per carpet Area) .	P.Sft	12.88		
24	Khurras on roof 2'x2'x6" (600 x 600 x 150 mm)	Each	1.00		
25	Bottom Khurras of brick masonry in cement mortar 1:6, 4'x2'x4½" (1200x600x113 mm) over 3" (75 mm) cement 1:4:8	Each	1.00		
26	Painting new surf ace:- Preparing surface and painting of fillets, framing, skirtings, pipes, gutters, and similar linear work no exceeding 6" (150 mm) girth:	%Rft	190.66		
27	Providing and fixing marble strip of any shade for dividing the mosaic flooring into panels (40 x 10 mm)	P.Rft	72.00		
28	Supplying and filling sand under floor; or plugging in wells.	%Cft	115.43		
29	Reinforced cement concrete in slab of rafts / strip foundation, base slab of column and retaining walls; etc and other structural members other than those mentioned above not requiring form work (i.e. horizontal in shuttering) complete in all respects:- Type C (nominal mix 1: 2: 4)	P.Cft	18.59		

30	Fabrication of mild steel reinforcement for cement concrete, including cutting, bending, laying in position, making joints and fastenings, including cost of binding wire and labour charges for binding of steel reinforcement (also includes removal of rust from bars.) Deformed bars (Grade-40)	%Kgs	24.24		
31	Cement concrete plain including placing, compacting, finishing and curing complete (including screening and washing of stone aggregate): Ratio 1:2:4	%Cft	19.79		
32	Dismantling brick work in lime or cement mortar.	%Cft	57.00		
33	Removing windows and sky lights with chowkat.	Each	1.00		
34	Supply and erection of PVC pipe for wiring recessed in walls including clamps inspection boxes, pull boxes, bends, tees, repairing surface, etc., complete with all specials:-				
	25 mm i/d	P.mtr	12.00		
	20 mm i/d	P.mtr	8.00		
35	Supply and erection of single core PVC insulated, PVC sheathed copper conductor, 250/440 volts grade cable (BSS-2004), in pre-laid PVC pipes/M.S. conduit/G.I. pipe/wooden strip batten/wooden casing and capping/trenches, etc. (rate for cable only)				
	3/0.029"	P.mtr	50.00		
	7/0.029"	P.mtr	30.00		
36	P/F PVC double layer Switch kit Faceplate with specified switch holes i/c the cost of switches / sockets / dimmer made of Hi-Life / Bush / Schneider, screws complete as approved and directed by the Engineer Incharge One way Gange Switch	Each	1.00		
37	Providing and fitting one piece European Coupled set of Water Closet (WC) and flushing Cistern of PORTA brand (full size) i/c the cost of CP/rubber connection, thimble, normal seat cover and rawal bolts complete in all respects as approved and directed by the Engineer Incharge.	Each	2.00		
38	Providing and fitting glazed earthen ware wash hand basin /vanity 56x40 cm (22"x16") including bracket set, waste pipe and waste coupling, etc.				
	i) white, with pedestal	Each	1.00		
	v) Under Counter Vanity Basin	Each	1.00		
39	comprising of 3-No Tee stop cocks, lever type Basin Mixer, double Bib Cock, open wall shower, Muslim shower, waste coupling and bottle trap etc. complete in all respect as approved and directed by the Engineer incharge.				
	3 No Tee Stop Cock	Each	2.00		
	Lever Type Basin Mixer	Each	1.00		
	Double Bib Cock	Each	2.00		
	Muslim shower	Each	2.00		
40	Providing and laying Prepolished Granite of specified thickness and shade of full width of approved quality laid with adhesive bond over 3/4" thick (1:2) cement sand mortar bed, complete in all respect as approved and directed by the Engineer Incharge	P.Sft	12.50		

41	Extra cost for making hole in Marble slab for fixtures, Sink, burners, basin Vanities i/c cost of bevelling of internal edge as approved and directed by the Engineer Incharge	Each	2.00		
42	Providing, fixing, testing and commissioning of μ -PVC (Unplasticized Polyvinyl Chloride) Nikasi/ SWV pipe, Dadex / Popular / Beta or approved equivalent manufacturer, plain / Bell Ended / Z - Joints conforming to BS 4514 / BS 5255 EN-1329 including the cost of specials and Solvents complete in all respects, as per drawings & specifications and / or as approved and directed by the Engineer Incharge.				
	3"(85 mm)	P.Rft	20.00		
	4"(110 mm)	P.Rft	15.00		
43	Providing, fixing, testing and commissioning of μ -PVC (Unplasticized polyvinyl Chloride) Nikasi/ waste pipe Fittings make of Dadex Popular/Beta or approved equivalent manufacturer, conforming to code EN-1329 including the cost of Solvents complete in all respect as approved and directed by the Engineer Inch				
	P-Trap 3"	Each	3.00		
	P-Trap 4"	Each	3.00		
	Vent Cowel 4" Dia	Each	2.00		
	Clean out 4" Dia	Each	2.00		
44	Providing, laying, testing and commissioning of POLYPROPYLENE RANDOM COPOLYMER (PPRC) water supply pipe made of (Dadex/Popular/ Beta/ BBJ) with specified pressure rating PN (PRESSURE NOMINAL)and conforming to DIN 8077-8078 code i /c cost of solvent ,specials,making jharries complete in all respect as approved and directed by Engineer Incharge.(Internal /External Diameters mentioned).PN-20 pipe	P.Rft	30.00		
				Total	
				Add 05% Pst	
				G.Total	